

Addendum No. 1

Work: All Work
Project: Fertile-Beltrami School Casework Replacement
Fertile, Minnesota
Foss #1755.01

Date Addendum Issued: April 25, 2018

Bid Submittal: May 1, 2018

To: All Planholders

Acknowledge receipt of this addendum. This Addendum forms part of Bidding Documents and modifies them as follows:

SPECIFICATIONS:

SECTION 06 4000 Architectural Woodwork:

Page 4, Paragraph 2.04 B, sub-paragraph 1, Change to:

“Provide at all countertops where sinks occur and at cabinet bases where sinks occur.” Moisture resistant particleboard is not required where sinks do not occur.

SECTION 06 4000 Architectural Woodwork:

Page 4, Paragraph 2.05, Clarification:

Structural cabinet body to be constructed with full sub-top per specifications, in lieu of what was shown in details.

Countertops to be constructed as specified, in lieu of what was shown in details.

SECTION 06 4000 Architectural Woodwork:

Page 5, Paragraph 2.06 C, Add:

“When providing heavy duty hinges, a minimum of three per door is required.”

DRAWINGS:

Sheet A1.1:

Second Level Reference Plan – Room 203. Provide (2) 6'-0"W x 4'-0"H marker boards on west wall of classroom as shown. Layout shall be similar to marker board and smartboard layout shown in elevation 3/A7.1. Coordinate final location of the smartboard with owner prior to installation of markerboards.

END OF ADDENDUM NO.1

