

ADDENDUM #1 – Friday, February 9, 2018

PLANS AND SPECIFICATIONS FOR:

Owner: MAYVILLE STATE UNIVERSITY – CHILD DEVELOPMENT PROGRAM

Project: CHILD DEVELOPMENT KITCHEN RENOVATION

Grand Cities Mall, Unit #A34, 1726 S Washington St, Grand Forks, ND

Architect's Project Number: 2017-26D

This Addendum is issued to **all registered plan holders** pursuant to the Instructions to Bidders. This Addendum serves to clarify, revise, and supersede information in the Project Manual, Drawings, and previously issued Addenda. Portions of the Addendum affecting the Contract Documents will be incorporated into the Contract by enumeration of the Addendum in the Owner/Contractor Agreement. The Bidder shall acknowledge receipt of this Addendum in the appropriate space on the Bid Form.

The date for receipt of bids is unchanged by this Addendum.

Monday, February 12, 2018 at 3:00 p.m. CDST

Bid Place **has changed** to: Grand Cities Mall, Unit #10, 1726 S Washington St, Grand Forks, ND

CLARIFICATIONS:

- Item #1 Mall is Open from 8:00am to 8:00pm. Mall is willing to allow access from back door at 6am.
- Item #2 Contractor to coordinate dumpster location out back door of space with Mall.
- Item #3 The fluid applied flooring in just flooring, no coved base. All wall base is 4" vinyl.

SPECIFICATIONS:

SECTION 01 50 00 – Temporary Facilities and Contrals

Item #1 Change Paragraph 1.2 to read as follows:

“1.2 TEMPORARY ELECTRICITY

A. Use Owner's existing power service.”

MECHANICAL ITEMS:

- Item #1 Mechanical Contractor to repipe hot and cold water that is runs over electrical panels to mop sink, to be below the panel to meet current building codes.
- Item #2 Dishwasher Drain: A drain hose, ¾" diameter and 6' long, is provided. This should be securely plumbed into the sink drain. Use care not to kink hose. See installation diagrams in this manual. Drain must have a minimum flow capacity of 4 gallons per minute.

DRAWINGS:

ITEM NO. 1 Sheet E1 - Dishwasher Circuit

- A. Owner furnished dishwasher is rated 120/208 Volt, 3 Wire, 37.7 FLA.
- B. Provide a 50 ampere, 2 pole circuit breaker in existing Cutler Hammer load center panel.
- C. Mount an existing Owner furnished 60 Ampere disconnect switch above/beside the dishwasher (field verify exact location).
- D. Provide a new three wire with ground to disconnect switch (3-#6, 1-#10 ground in 1-1/4" conduit from the Cutler Hammer panel to the dishwasher disconnect.

.END of ADDENDUM.